

The TOP Project at Belle II

Toru Iijima

*Kobayashi-Maskawa Institute
Nagoya University*

for Belle II B-PID group
2015.11.12




Kobayashi-Maskawa Institute
for the Origin of Particles and the Universe

Talk Outline

- Status of Belle II
- Overview of the Belle II TOP Counter
- Status of detector construction
 - Module production
 - Quartz optics
 - Mechanics
 - MCP-PMT
 - Readout electronics
 - Calibration system
- Summary

Detailed information available via webpages
of “BPAC review” meetings.
→ belle2.kek.jp




SuperKEKB/Belle II

- New intensity frontier facility
- Target luminosity ;
 - $L_{\text{peak}} = 8 \times 10^{35} \text{ cm}^{-2} \text{s}^{-1}$
 - $L_{\text{int}} > 50 \text{ ab}^{-1}$ by early 2020's.










$\Rightarrow \sim 10^{10}$ BB, $\tau^+\tau^-$ and charms per year !

“Nano-beam” scheme
proposed by P.Raimondi




	SuperKEKB LER/HER	KEKB LER/HER
E(GeV)	4.0/7.0	3.5/8.0
ϵ_x (nm)	3.2/4.6	18/24
β_y at IP(mm)	0.27/0.30	5.9/5.9
β_x at IP(mm)	32/25	120/120
Half crossing angle(mrad)	41.5	11
I(A)	3.6/2.6	1.6/1.2
Lifetime	$\sim 10\text{min}$	130min/ 200min
$L(\text{cm}^{-2}\text{s}^{-1})$	80×10^{34}	2.1×10^{34}

Belle II collaboration (>600 from 99 institutes)




Getting Ready for Phase 1




Schedule

- 2016.1: start beam commissioning
- 2017: data taking without vertex detector
- 2018: data taking with full detector



Belle II TOP counter


- Cherenkov ring imaging using precision timing ($\sigma_{\text{TS}} < 50\text{ps}/\text{photon}$).
- Very compact, suitable for collider geometry.
- Focusing mirror for correcting chromatic dispersion effect.
- Imaging w/ expansion block + 2-layer MCP-PMT.



Collaboration of Japan + US + Slovenia + Italy



Group leader : Jim Fast (PNNL), sub-leader: T.I.

Beam Test @ Spring-8/LEPS (June 2013)




More results (also with conventional CFD readout) → talks by K. Inami @ RICH2013, K. Matsuoka @ TIPP2014

Belle II TOP Quartz Bar Box (QBB)



16 modules are connected by “z beam”
to make a rigid cylinder



sag < 0.5 mm
required

Belle II TOP Quartz Optics

Bar (photon propagation)



- $L = 1250 \pm 0.5\text{mm}$
- $W = 450 \pm 0.15\text{mm}$
- $H = 20 \pm 0.1\text{mm}$
- Flatness (S_1, S_2) $\leq 6.3\mu\text{m}$
- Local flatness (S_1, S_2) $\leq 1.8\mu\text{m}$ (200mm area)
- Surface roughness $\leq 5 \text{ \AA rms}$ (S_1-S_4)
- $S_1 \perp S_{3,4} \leq 20 \text{ arcsec}$, $S_1 // S_2 \leq 4 \text{ arcsec}$

Mirror (image focusing)

- $L = 100 \pm 0.15 \text{ mm}$
- $R = 6500 \pm 100 \text{ mm}$

Prism (image expansion)


- $L = 100 +0.1/ -0.25 \text{ mm}$
- $W = 456 \pm 0.15 \text{ mm}$
- $H = 51 \pm 0.1 \text{ mm}$ (PMT side)
- Angle (S_1-S_2) $= 18.07 \pm 0.04 \text{ deg.}$



4 bars produced by Okamoto Optics Works
29 of 34 bars are at hand (completed by Feb. 2016)




Delivery completed




Delivery completed

Construction flow overview






TOP Assembly Facility @ Fuji B4



- TOP assembly room (ver.3) managed by Nagoya / KEK team
 - ◆ Class 100-1,000 large cleanrooms + class <5,000 buffer room + booth
 - ◆ Cleanroom 1: Quartz gluing / QBB assembly
 - ◆ Cleanroom 2: Quartz testing / Temporal(?) quartz storage
 - ◆ 2nd buffer booth: PMT Assembly / cleaning space for QBB parts

Optics QA : Bars


- QA measurements are made in the clean room #2 at KEK.
- Inspect bulk transmission, reflectivity and chips.



$$I_0(1 - R_0)\tau(1 - R_1) = I_1 \quad (I_1 - R_1) = (I_0 - R_0) \cdot \alpha^N \cdot \exp\left(-\frac{L}{\Lambda} \cdot \sqrt{1 + (Nh/L)^2}\right)$$

R_0, R_1 : Calculated by
Fresnel equations. Laser is
polarized as S-wave for
reflectivity measurement.

Bulk Trans. Internal Reflect.



Laser wavelength: 405 nm
Ave. Bulk Trans.: (99.55 ± 0.07) %/m
Ave. Internal. Reflect.: (99.984 ± 0.008) %


Assembling steps



Optics: alignment, gluing, curing and aging (~2 weeks).

Enclosure: gluing CCDs and LEDs, integrating fiber mounts.

QBB: strong back flattening, button & enclosure gluing.



Put on a cart. PMT and front-end integration, performance check.




QBB assembly and gas sealing.

Move optics to QBB using the “lifting jig”.

Quartz Gluing

- We use EPOTEK-301 for all joints.
 - Gluing procedure is based on dry runs + some R&D for details
 - Taping (+ curtain for prism-bar joint)
 - Centrifuge for eliminating bubbles
 - Glue injection with a trolley
 - Cleaning, curing, ...
- Remove extra glue after ~6hrs
Remove tape and clean optics after ~27hrs

Gluing for module 01




- Small delamination observed in prism-bar joint for the module01.
- Gluing procedures were revisited, and many studies were made.
- We haven't seen similar phenomena for later modules.

We use Teflon tapes for later modules



Glued Optics (Module 01)

16







QBB preparation

- Measure flatness of the honeycomb panels.
- Attach strong-back, tune and test stability.
- Assemble enclosure
 - Align inner-panel and enclosure < 0.06mm.
- Install LEDs, cameras, spring holders, fiber holders






QBB Preparation (PEEK button)






- Quartz are supported by PEEK buttons.
- Height of the PEEK buttons need be adjusted very carefully.



More Pictures from QBB Preparation




Installation of Optics to QBB




Completion of Optics + QBB (Nov.10)

21





PMT Module Assembly

- PMT modules are assembled in the Fuji FI clean booth.
- The assembly procedure has been fixed.
- Every module is tested for HV after assembly.





Silicon rubber TSE3032 (before curing) to be filled between the PMTs and the wavelength cut filter



MCP-PMT Mounting

- Designed so that PMT+ readout modules can be replaced from the access hatch.
- Mounting method has been established with the prototype.
 - Optical cookies for WL-filter–Prism interface
 - Pogo pins for PMT – Readout interface

Installation for module 01



Production schedule


Module assembly period Module assembly done

Long national holidays/vacations (no work)

Collaboration meetings, reviews or workshops

- Module production moves smoothly now. ~3 weeks per module
 - Finished Module10 assembly as scheduled

Current status



Module01 at Fuji F1



Module03,04
at Fuji B4 tent
in testing for
installation



Module02, 05-07 at Fuji B4 tent







Module08,09 at Buffer2


In clean room,
Module10 gas sealed
Module11 optics glued.

Readout Electronics + HV

- MCP-PMT signal is readout by newly developed “IRS” ASICs.
 - Waveform sampling
 - High density, multi-hit buffering
 - 512ch/module, 30kHz trigger rate
 - Clock jitter measured with test pulse is 20ps.




Production Workflow





All circuit boards fabricated, assembled

Cable harnesses in fabrication, HV board PoGO pins & potting

Production Laser Testing (at UH)



10




Readout meets experiment needs

Production status

Test bench at U. South Carolina

- Testing is going well.
- More manpower for HVB going to IU in November.
- Rework is needed to get sufficient number of SCROD.



Board	# Required	# Fabbed	# Grade A*	# Grade B**	# Grade F***	Untested
Front	136	164	125	15	13	11
High Voltage	68	90	17 28	0 1	0	73 61
SCROD	68	77	63	0	14	0
Carrier	272	332	213 247	41 74	18 9	63 2

* Grade A = perfect

** Possibly usable

*** Requires rework prior to using

Update (G. Varner)


MCP-PMT Production




Hamamatsu 1"
16-ch MCP-PMT

- Total of 611 MCP-PMTs have been ordered
 - Phase1 production completed: 515 total (285 conventional, 230 ALD)
 - Lifetime extension R&D is using 42 (will not be used in Belle II)
 - Phase 2 production of extended lifetime tubes will produce final 54
 - Belle II will have a total of 569 tubes (512 + 57 spares).

We have repeated the PMT measurements to confirm no performance degradation.



Measured QE



- Average QE at 360 nm
- Conventional: 28.1%
 - ALD: 29.1%

Photoelectron flux, accumulated charge

1 MHz/PMT at 5×10^5 gain at design luminosity


→ about $1 \text{ C/cm}^2/50\text{ab}^{-1}$ normal type MCP PMTs

Rate plot can be turned into an accumulated charge (C/cm^2) plot

Plot the accumulated charge for expected summer shutdown luminosities

Min. lifetime,
ALD MCP PMT
($>3 \text{ C/cm}^2$)

Average lifetime,
Conventional
MCP PMT
($0.3\text{-}1.8 \text{ C/cm}^2$)



2023: 50/ab

2022: 38/ab

2021: 26/ab

2020: 14/ab


2019: 5/ab

P. Krizan

Conventional MCP-PMTs have to be replaced at some point.

Recent Lifetime R&D

- Test 6 methods of processing to improve the lifetime.
- Produce 6 samples of each method for life test.
 - Test 4 samples at Nagoya and 1 at HPK.
- Produce 8 samples with the good methods combined, and measure their lifetime for confirmation.





- Estimated integrated output charge in Belle II:
1.5-3 [$\text{C}/\text{cm}^2 / 50 \text{ ab}^{-1} / 5 \times 10^5 \text{ gain}$]
 - We measured the lifetime for some MCP-PMTs.
 - Conventional: 0.3-1.8, average $1.1 \text{ C}/\text{cm}^2$
 - We will exchange them with new ones when their QEs drop.
 - ALD: 3-13.5 (or longer), average $8.6 \text{ C}/\text{cm}^2$
- ↑ We want to improve this for future use.

The lifetime of every sample is expected to be longer than $15 \text{ C}/\text{cm}^2$.

Plan for MCP-PMT Installation



- We have three types of MCP-PMTs:
 - 283 conventional MCP-PMTs (lifetime: $0.3\text{-}1.8 \text{ C/cm}^2$, average 1.1 C/cm^2)
 - 231 normal ALD MCP-PMTs ($>3 \text{ C/cm}^2$, average 8.6 C/cm^2)
 - 65 life-extended ALD MCP-PMTs under production (at least 15 C/cm^2)
(cf. Predicted output charge: $1.5\text{-}3.1 \text{ C/cm}^2/50 \text{ ab}^{-1}$ at 5×10^5 gain)
 - Conventional ones have to be replaced in 2020 or 2021 summer.
 - Average QE of each module is almost the same.




Laser Calibration System

- Developed by Italian group (Padova/Torino)
- w/ PiLas laser, PLC splitter, SM fiber, MM fiber, GRIN lens.




TOP light distribution system



Probably three peaks by direct photons and those reflected once and twice





Module Installation



Module Testing Plan

- Primary test for every module
 - Electronic charge injection
 - Laser test in modules
 - Cosmic test without tracking
- Cosmic test with precision tracking for subset of modules (one or two)
 - Use CDC for precision tracking
 - Also as an integration test of Belle II DAQ
- Global cosmic ray test after installation
- A beam test could occur after installation
 - If a compelling reason emerges (e.g. calibration of p.d.f.)

CR test stand at Fuji



CDC at Tsukuba exp. hall



Summary

- Belle II TOP is the first realization of a detector using internally reflected Cherenkov lights with **precise Time-Of-Propagation** measurement.
 - After >15 years of R&D + very large efforts.
- Construction is progressing very well, after solving many many problems.
- Many many experiences (quartz optics, MCP-PMT, mechanics) have been accumulated.
 - We are happy to share knowledge, know-hows, ...
- Many more to learn (probably) for stable operation, analysis, etc.




Stay tuned ! & Let's keep in touch !

Danke schön !

Backup

Quartz Alignment



- Quartz alignment is done with a gluing stage, autocollimator, and laser sensors.



Optics QA : Mirror (SN002)

- Measured at Cincinnati (M. Belhorn, B. Pal, A. Schwarz)

Test (Specification)	Vendor Measurement	Cincinnati Measurements		
		Date	Location	Measurement
Edge Chips ($< 20 \text{ /m}$)	16 ("Chippy")	03/15/2014		0 additional
Reflectivity ($> 85\%$ for $300 - 600 \text{ nm} \lambda$)	87.26 %	06/10/2014 06/10/2014 06/13/2014	$y = 8.8 \text{ mm}$ $y = 10.0 \text{ mm}$ $y = 12.5 \text{ mm}$	$88.29 \pm 0.03 \%$ $88.09 \pm 0.02 \%$ $87.81 \pm 0.03 \%$
Transmittance		07/21/2014		$99.921 \pm 0.052 \%/\text{m}$
Radius ($6500 \pm 100 \text{ mm}$)	"Approx. 6497 mm"	06/10/2014 06/10/2014 06/13/2014	$y = 8.8 \text{ mm}$ $y = 10.0 \text{ mm}$ $y = 12.5 \text{ mm}$	$6501.38 \pm 0.15 \text{ mm}$ $6500.15 \pm 0.15 \text{ mm}$ $6499.04 \pm 0.14 \text{ mm}$
		Overall Fit*:		$6500.15 \pm 0.07 \text{ mm}$





* Statistical error only, applies to following tables.

Optics QA: Prism


- Inspected for chips, angle and transmittance at Cincinnati (M. Belhorn, B. Pal, A. Schwarz)

Prism	Chips	Transmittance	Angle
449006	0	$99.934 \pm 0.044 \text{ \%}/\text{m}$	$18.089^\circ \pm 0.007^\circ$
449008	0	$99.774 \pm 0.043 \text \%/\text{m}$	$18.091^\circ \pm 0.007^\circ$
449009	0	$99.935 \pm 0.044 \text \%/\text{m}$	$18.073^\circ \pm 0.007^\circ$
449010	0	$99.703 \pm 0.043 \text \%/\text{m}$	$18.086^\circ \pm 0.005^\circ$




High Purity N2 System

- We will seal QBB and test leak.
- High purity N2 system is ready in Fuji hall



Lucien Cremaldi
(Mississippi)



Gas sealing

- QBB panels, side Rails, FWD endplate, prism enclosure were sealed with Si glue.
- Tested with Restek Electronic Leak Detector + Pure N2 (& G1 Ar)
 - Significant leaks were found in the prism enclosure through the mounts for CCD cameras, LED, fibers and others (fixed now).
- Started to flow pure N2, and measure dew point.
 - < -51 degC. (34.31ppm) achieved
 - Target is - 60 deg (11 vol.ppm) with the inlet flow rate of 0.5L/min. and pressure < 1 kPa.

